



*Stennis Space Center*

# Developments in test facility and data networking for the Altitude Test Stand at the John C. Stennis Space Center


## A General Overview

Phillip W. Hebert

SSC Electrical Design Engineering (EA-31)

(228) 688-2995

[Phillip.W.Hebert@nasa.gov](mailto:Phillip.W.Hebert@nasa.gov)




# Developments in test facility and data networking for the Altitude Test Stand at the John C. Stennis Space Center – A General Overview




*Stennis Space Center*

**Space Shuttle Main Engine Test  
@ A2 Test Stand**

**RS-68 650 klbf  
@ B1 Test Stand**



**Fastrac 60 klbf  
@ B2 Test Stand**





# Developments in test facility and data networking for the Altitude Test Stand at the John C. Stennis Space Center – A General Overview



*Stennis Space Center*

- ◆ NASA/SSC's Mission in Rocket Propulsion Testing Is to Acquire Test Performance Data for Verification, Validation and Qualification of Propulsion Systems Hardware
  - Accurate
  - Reliable
  - Comprehensive
  - Timely
- ◆ Data Acquisition in a Rocket Propulsion Test Environment Is Challenging
  - Severe Temporal Transient Dynamic Environments
  - Large Thermal Gradients
  - Vacuum to 15k psi pressure regimes
- ◆ SSC Has Developed and Employs DAS, Control Systems and Robust Instrumentation that Effectively Satisfies these Challenges
- ◆ The Following Presentation Reviews SSC's Data Acquisition and Controls Architectures



# Agenda

*Stennis Space Center*

- ◆ Background – SSC EE Org & Test Facilities
- ◆ High/Low Speed Data Acquisition Systems
- ◆ Control Systems
- ◆ Video Systems
- ◆ Network Architecture



## Stennis Space Center

```

graph TD
    JE[JE Project Manager] -.-> PM[A-3 Project Manager PA20]
    MSFC[MSFC Representative] -.-> PM
    PM --> IBMT[A-3 IBMT Support PA00]
    PM --> Env[A-3 Environmental Lead RA02]
    PM --> CE[A-3 Chief Engineer EA00]
    PM --> SEL[A-3 Systems Engineer Lead EA51]
    PM --> DML[A-3 Design Mechanical Lead EA32]
    PM --> DAL[A-3 Design Analysis Lead EA33]
    PM --> OEL[A-3 Operations Electrical Lead EA21]
    PM --> OML[A-3 Operations Mechanical Lead EA22]
    PM --> OFL[A-3 Operations Facility Lead EA10]
    PM --> CL[A-3 Construction Lead RA10]
    PM --> SML[A-3 Safety and Mission Assurance Lead QA20]
    PM --> PL[A-3 Procurement Lead BA33]
    
```


**Matrix**  
-----  
**Project Support**

## Reach back into respective elements



# Design & Analysis Division

*Stennis Space Center*



## Organization Goal:

- **Develop and maintain propulsion test systems and facilities engineering competencies**
  - Unique and focused technical knowledge across respective engineering disciplines applied to rocket propulsion testing. e.g.,
    - Materials selection and associated database management
    - Piping, electrical and data acquisition systems design for cryogenic, high flow, high pressure propellant supply regimes
    - Associated analytic modeling and systems analysis disciplines and techniques
    - Corresponding fluids structural, thermal and electrical engineering disciplines



# SSC Test Facilities

*Stennis Space Center*



## AB-Complex

**A-1**

Full Scale Engine Devt. & Cert

**A-2**

J-2X

SSME



## B-1/B-2

Full Scale Engine/Stage  
Devt. & Cert

RS-68/ARES



*Components  
...Engines  
... Stages*



# SSC Test Facilities (continued)

## E-Complex

*Stennis Space Center*



### E-1 Cells 1, 2, 3

High Press., Full Scale  
Engine Components


J-2X



### E-2 Cell 1

High Press.  
Mid-Scale  
& Subscale

J-2X



### E-3 Cell 1


E-2 Cell 2  
Low Press. Mid-Scale  
& Subscale, Stage

High Press. Small-Scale  
Subscale

TGV

### E-3 Cell 2





# SSC Test Facilities (continued)

A-3

*Stennis Space Center*

**Conceptual View –  
A3 Test Stand**







# SSC Test Facilities (continued)



*Stennis Space Center*






# Typical Test Articles

*Stennis Space Center*

## Integrated Powerhead Demonstrator




LR-89



# Test Facility Electrical Systems

*Stennis Space Center*


- ◆ Communications System
- ◆ **Control System**
- ◆ Facility Fire Alarm System
- ◆ Fire & Gas Leak Detect System
- ◆ Grounding System
- ◆ **High Speed Data Acquisition System**
- ◆ Lighting System
- ◆ Lightning Protection System
- ◆ **Low Speed Data Acquisition System**
- ◆ Aural Warning System
- ◆ Power Distribution System
- ◆ Uninterruptible Power System
- ◆ **Video System**
- ◆ **Interconnecting Network**



# Typical Test Facility Electrical System Layout

Stennis Space Center

## Historical Overview of Systems at SSC



Test Control Center

Signal Conditioning Bldg


Test Article



# Typical Test Facility Electrical System Layout

Stennis Space Center

## A-3 Test Stand Electrical Systems & Interactions






# Typical Test Facility Electrical System Layout

Stennis Space Center

## A-3 Test Stand Electrical Systems Software Data Flow & Interactions





# Test Control Centers –




Currently in Place

*Stennis Space Center*



A2 TCC



Test  
Conductor's  
Station



E2 TCC



# Signal Conditioning Buildings (SCB) –

## Current Uses & Installations

*Stennis Space Center*


E1 SCB  
Signal  
Conditioning  
Rack




E2 Cell 1  
SCB 1  
Controls  
Racks



E2  
SCB's  
1 & 2







# Signal Conditioning Buildings (SCB)



Stennis Space Center

## A-3 Test Stand SCB Location





*Stennis Space Center*


# High Speed Data Acquisition Systems (HSDAS)



# High Speed Data Acquisition System

*Stennis Space Center*

- The High Speed Data Acquisition System is used to record rocket engine or component data from a variety of dynamic sensors.
  - Sampling rates are normally an order of magnitude in sample rates compared to the Low Speed Data Acquisition System.
  - High speed data provides the Analyst with information about the dynamic environment/condition of a test article. The data feeds models that characterize the performance of the test article or allows the analyst to help determine the health of the hardware.
  - The data is typically analyzed in the frequency domain.
  - Challenges to recording good high speed data include the environment (high temperatures, vibration, high flow, cryogenic temperatures, high pressure), proper cabling, appropriate sensor selection, and numerous other considerations.



# High Speed Data Acquisition Systems

*Stennis Space Center*

- ◆ DataMAX II (New to be used for A-3)-  $\geq$  200,000 Samples Per Second (**Binary & Decimal Sampling**)
  - AB Complex (RS-68, J-2X)
  - E Complex
  - Planned for use on A-3



# Typical High Speed Data Acquisition System Instrumentation

*Stennis Space Center*

FACILITY	SPECIAL TEST EQUIPMENT	TEST ARTICLE
<p>Typical Instrumentation not always in the Catalog</p> <ul style="list-style-type: none"><li>• Special Ranges</li><li>• Temp Compensation</li><li>• Special Materials</li></ul>	<p>Accelerometer Strain</p>	<p>Dynamic Pressure Accelerometer Strain Proximity Speed</p>


**Typical High Speed DAS  
Instrumentation**



# Typical High Speed Data Acquisition System Instrumentation



*Stennis Space Center*



Strain



Dynamic Pressure



Speed



Accelerometer



# Planned A-3 High Speed Data Acquisition System

Stennis Space Center

## TEST STAND / TEST CELL

INTERCONNECT  
CABLING  
RECEPTACLE  
BOXES (RBs) &  
TEBs

SENSORS &  
TRANSDUCERS

T=0 FROM CS

IRIG-B TIME  
SOURCE

## SIGNAL CONDITIONING BUILDING (UL)

SIGNAL  
CONDITIONERS  
& AMPLIFIERS

CALIBRATION  
CONTROL

PATCH  
PANELS

Master  
Recorder

Slave

Master  
Recorder

Slave

Master  
Recorder

Slave

Master  
Recorder

HSDAS  
ETHERNET  
SWITCH (SCB)

FIBER OPTIC  
CABLE

## TEST CONTROL CENTER

TO SDC

FIBRE-  
CHANNEL

SSC LAN

A-3 LAN  
SERVER

DATA  
PROCESSING  
TRANSMISSION  
PC

RECORDER /  
CONTROL  
WORKSTATION  
(TCC)

A-3 TEST  
FACILITY  
LAN HUB

HSDAS  
ETHERNET  
SWITCH (SCB)


MSFC

PWR



*Stennis Space Center*

# Low Speed Data Acquisition Systems



# SSC's Low Speed Data Acquisition Systems

*Stennis Space Center*


- ◆ **Data acquisition, recording, real time display, data acquisition**
  - **Data types:** Low frequency Analog Data, Discrete (event) Data, Pulse Data from flow meters and speed sensors
    - ◆ **E-Complex Digitizer** - ~ 200 samples per second or greater
    - ◆ **AB-Complex Digitizer** - ~ 200 samples per second or greater
    - ◆ **A-3 Test Stand** – ~ 200 samples per second or greater



# E-Complex Low Speed Data Acquisition System Architecture

Stennis Space Center

## Historical Overview of LSDAS at SSC – E-Complex





# AB-Complex Architecture

## Low Speed Data Acquisition System


Stennis Space Center

### Historical Overview of LSDAS at SSC – AB-Complex

OUTER CORE of TEST STAND

INNER CORE of TEST STAND

TEST CONTROL CENTER





# AB-Complex Architecture

## Low Speed Data Acquisition System

*Stennis Space Center*

### Historical Overview of LSDAS at SSC – AB-Complex

- ◆ The AB-Complex LSDAS consists of four test stand systems:
  - A1, A2, B1, B2 (B1/B2 one structure with two distinct sides)
    - ◆ Systems contain  $\geq 500$  analog input channels and  $\geq 700$  digital input channels
    - ◆ Each system contains a primary and secondary system for redundancy. Data from the secondary system is only processed if a problem occurs on the primary system.



# AB-Complex Architecture

## Low Speed Data Acquisition System

*Stennis Space Center*

### Historical Overview of LSDAS at SSC – AB-Complex



- ◆ Fully populated analog box
  - $\geq 200$  analog input channels
- ◆ Fully populated discrete box
  - $\geq 400$  digital input channels



# AB-Complex Architecture Low Speed Data Acquisition System

*Stennis Space Center*

## Historical Overview of LSDAS at SSC – AB-Complex



### ◆ Model 8300


- **Programmable**
  - ◆ Gain, filter, excitation
- **Automated calibration**
  - ◆ Voltage Insertion
  - ◆ Shunt
  - ◆ Rcal
- **Various Mode Cards**
  - ◆ Strain Gauge
  - ◆ Full Bridge , Half Bridge
  - ◆ RTD
  - ◆ Thermocouple
- **Measurements**
  - ◆ Strain Gauges
  - ◆ Pressure Transducers
  - ◆ RTD's
  - ◆ Thermocouples



# Proposed A-3 Low Speed Data Acquisition System Architecture

Stennis Space Center

## A-3 Test Stand Proposed LSDAS





# Low Speed Data Acquisition System Software



Stennis Space Center

## Software:

### ◆ Existing functionality

- All of the E-Complex Low Speed DAS software is developed in LabVIEW
  - ◆ LSDAS Operational and Control Software
  - ◆ Display Screens
  - ◆ Calibration Software
  - ◆ Measurement System Analysis (MSA's)
  - ◆ "Near" real-time data transmissions

### ◆ Proposed for A-3

- Currently considering option of having vendor provided software or Pratt-Whitney Rocketdyne developed Stennis Data Acquisition (SDAS) software for the following functions:
  - ◆ LSDAS Operational and Control Software
  - ◆ "Near" real-time data transmissions
  - ◆ Display Screens
  - ◆ Calibration Software
- The Measurement System Analysis (MSA's) function is planned to be developed in-house by NASA Engineering & Sciences Directorate (E&SD).



# AB-Complex Architecture Low Speed Data Acquisition System

*Stennis Space Center*

## Software

### ◆ Data Acquisition and Real-time Display

- ◆ Provides for the control of the data acquisition process and the distribution of data for real-time display
- ◆ Combines both the analog and discrete data

### ◆ Measurement System Analysis


- ◆ Software originally and methodology developed by Rocketdyne
- ◆ Purpose is to quantify a system precision for the LSDAS by evaluating the drift over time of the data system.
- ◆ It consists of a two point calibration performed every hour during an eight hour time span. This is to simulate the maximum time between a pre-test calibration and a test.



# Low Speed Data Acquisition System – Calibration Control

Stennis Space Center

## Calibration Control





# AB-Complex Architecture

## Low Speed Data acquisition System

*Stennis Space Center*

### Calibration Software

- ◆ Provides computer controlled setups and calibration of the Signal Conditioners.
- ◆ Signal Conditioning Setup
  - Select gain, filter
  - Setup and adjustment of individual signal conditioners and amplifiers
- Calibration
  - Automatic calibrations on any number of selected signal conditioners
  - Calibrate all active measurements pre-test
  - Calibration Types
    - ◆ Shunt Calibration
    - ◆ Voltage Substitution
    - ◆ Excitation Power Supply Calibration
    - ◆ External Calibration



# Typical Low Speed Data Acquisition System Instrumentation

Stennis Space Center

Static Pressure		Static Pressure
Radiometer		Temperature
Temperature	Static Pressure	Flow
Flow	Temperature	LVDT
LVDT	Flow	Strain
Level	LVDT	Proximity
Load Cell	Strain	Speed
FACILITY	SPECIAL TEST EQUIPMENT	TEST ARTICLE

- **Standard Instrumentation - Not always in the Catalog**
  - Special Ranges (Cryogenics, Hundreds of Degrees F )
  - Special temperature compensation circuits
  - Special Materials
  - Extremely High Pressures
  - Vacuum pressure transducers - Specific to the A-3 Test Stand



# Typical Low Speed Data Acquisition System Instrumentation

Stennis Space Center

## Pressure



Transmitter



Delta P



Pressure

## Strain




Strain Gauges

## Temperature



Thermocouples



RTD's



Transmitter

## Flow



Venturi Flowmeter



Turbine Flowmeter

## Speed



Speed Probe



*Stennis Space Center*

# Control Systems



# Control Systems

*Stennis Space Center*

- The **Control System** manages the test complex and rocket engine or component systems during day-to-day operations and testing while maintaining a safe environment allowing for orderly test shutdown and making facility systems safe in emergency situations.
  - Programmable Logic Controllers (PLCs) form the backbone of the SSC Control Systems – New term Programmable Automation Controllers (PAC).
  - PLCs primary functions are to sequence rocket engine or component tests and maintain daily operations.
  - Hard-wired controls are provided as a backup to the PLCs.



# Control Systems Functions

*Stennis Space Center*

## ◆ Day to Day Operations

- Unloading cryogenics/propellants (Oxygen, Hydrogen, Nitrogen, Methane, etc.)
- Propellant transfers from storage to run tanks
- Pumping up bottle pressures (Nitrogen, hydrogen, helium etc.)
- Gas leak and fire detection.
- Engine drying
- Facility Readiness Test (FRTs)
- Redline cut checks (Redlines are measurements that are monitored by the PLC for the purpose of initiating an immediate shut down when out of tolerance.)




# Control Systems Functions

*Stennis Space Center*

## ◆ Test Day Operations

- Propellant Transfers
- Engine chill down and prep
- Blue-line monitoring (Permissives to start test.)
- Test stand valve sequencing and control during hot fire test
- Redline monitoring during hot fire test
- Performs a controlled shutdown of the engine
  - ◆ Critical valves are also wired to a backup PLC or timed relays
- For the A-3 Test Stand, proper control of the Chemical Steam Generator (CSG) system is also required.



# A-3 Test Stand Control System

*Stennis Space Center*

## ◆ Seven PLC functions:

- Facility Control
- CSG Control
- CSG Control Backup
- Blue-Line and Redline Monitoring & Test Sequence Control
- Fire and Hazardous Gas Detection
- Dock – Propellant Transfer
- Calibration Control

## ◆ Generic Ladder Logic is envisioned


- System is configured entirely through Excel or Database
- Excel tables and/or Database can be configured in advance and downloaded on test day.
- Excel tables and/or Database can be archived for historical reference



# E1 Control System Layout

Stennis Space Center

## Historical Overview of Controls System at SSC – E1






# E1 PLC Network Design

*Stennis Space Center*

## Historical Overview of Controls System at SSC – E1





# Typical E1 SLC Programmable Logic Controller (PLC) Installation

*Stennis Space Center*

## Historical Overview of Controls System at SSC – E1

### E1 PLC Cabinet

- Dedicated STE PLC for Cell 2

DO      AI

AO      DI

- Shared Display PLC~

AI


DI





# Proposed A-3 Control System Architecture

Stennis Space Center





## Stennis Space Center






# SSC PLC Architecture Changes

*Stennis Space Center*

- Migration to faster PLCs in a Distributed Architecture outside the E1 Test Facility

- A-Complex Redline System
- A-Complex Fire & Gas Leak Detect System
- B-Complex Redline System
- B-Complex Fire & Gas Leak Detect System in design
- E3 Redline System



Modernized PLC



# Test Control Center with Graphical User Interface (GUI) Screens




*Stennis Space Center*





# InTouch by Wonderware GUI

Stennis Space Center





*Stennis Space Center*

# Video System



# A-3 Test Stand Video System


*Stennis Space Center*

- The **A-3 Video System** is envisioned to be a digital media video recording system. To this date at SSC, video recording system has been based upon a system that records to video tapes.
- **A-3 TEST STAND VIDEO REQUIREMENTS:**
  - Must record digital data to either hard drive or DVD.
  - Low Speed frame rate of ~30 frames per second (fps). High Speed frame rate of ~200 fps or greater.
  - Recording time of  $\geq$  steam generation time plus margin, minimum for both Low and High-Speed Video Systems.
  - Recording must be remote from the camera.
  - Cameras and/or enclosures must operate at expected vacuum pressures.
  - Must digitally stream real time Low Speed test video off-site.
  - Must support Infrared (IR) video.



# A-3 Test Stand Video System

Stennis Space Center





*Stennis Space Center*

# A-3 Test Facility Network Architecture



# A-3 Network Architecture Description

*Stennis Space Center*


- The **A-3 Network System** is designed to provide overall network connectivity between all of the sub-networks required for the A-3 Electrical Systems.
- **A-3 TEST STAND NETWORK REQUIREMENTS:**
  - Test data network must be physically isolated from facility data network.
  - Transmission of “near” real-time data and video must use outgoing only physical connections.
  - Provide method of transmitting post-test data outside of Test Facility network.
  - Provide a means of digitally transmitting “deterministic” LSDAS data to the Control System.



# A-3 Network Architecture Block Diagram

Stennis Space Center

## A-3 Test Facility LAN







# A-3 Network Architecture Block Diagram

Stennis Space Center

## Typical Control System Type Inputs



## Networked Control System Connection





# A-3 Network Architecture Block Diagram



Stennis Space Center

- Advantages of network connectivity:

- Reduced Input modules to the controller:

- Reduce costs of acquiring unnecessary analog input modules
- Reduce costs of wiring channels to the CS
- Reduce effort of programming required for analog inputs
- Reduce schedule by not requiring additional wiring, programming, and activation time.
- Reduce space required to house CS channels
- Reduced potential failure points with less hardware
- Potentially increased scan speed with fewer modules to query
- Data consistent between LSDAS and Controls Systems

- Disadvantages of network connectivity:

- Lack of comparison of measurements between systems (Controls vs. DAS)
- Reduced independence of Controls operations.

Controls blindness if DAS fails



# Summary

*Stennis Space Center*

- ◆ NASA/SSC's Mission in Rocket Propulsion Testing Is to Acquire Test Performance Data for Verification, Validation and Qualification of Propulsion Systems Hardware
  - Accurate
  - Reliable
  - Comprehensive
  - Timely
- ◆ Data Acquisition in a Rocket Propulsion Test Environment Is Challenging
  - Severe Temporal Transient Dynamic Environments
  - Large Thermal Gradients
  - Vacuum to high pressure regimes
- ◆ A-3 Test Stand Development is equally challenging with respect to accommodating vacuum environment, operation of a CSG system, and a large quantity of data system and control channels to determine proper engine performance as well as Test Stand operation.
- ◆ SSC is currently in the process of providing modernized DAS, Control Systems, Video, and network systems for the A-3 Test Stand to overcome these challenges.